



ऑयल इंडिया लिमिटेड
(भारत सरकार का उद्यम)
Oil India Limited
(A Government of India Enterprise)

Regd. Office: P.O. Duliajan, Distt. Dibrugarh, Assam-786602
Corp Office: Plot No. 19, Sector 16-A, Noida-201301, Uttar Pradesh
CIN: L11101AS1959GOI001148 Website: www.oil-india.com

Ref. No. OIL/SEC/32-33/NSE-BSE/Reg. 30
Dated: 01.08.2020

National Stock Exchange of India Ltd.

Exchange Plaza,
Plot No. C/1, G Block,
Bandra-Kurla Complex,
Bandra (E),
Mumbai - 400 051

BSE Ltd.

Department of Corporate Service,
Phiroze Jeejeebhoy Towers,
Dalal Street,
Mumbai- 400 001

Scrip: OIL

Scrip: 533106

**Sub: Press Release - Blowout in Gas Well of the Company at Baghjan,
Tinsukia District, Assam**

Ref: Regulation 30 of the SEBI (Listing Obligations and Disclosure
Requirements) Regulations, 2015

Sir/Madam,

Further to our press release dated 30.07.2020 on the captioned subject, we submit herewith the Press Release dated 31.07.2020 for your information & records please.

Thanking you,

Yours faithfully,
For Oil India Limited

(A.K. Sahoo)
Company Secretary &
Compliance Officer

Press Release

Blowout in Gas Well of Oil India Limited at Baghjan, Tinsukia

31st July 2020

Environmental Impact Assessment

- **TERI Study on Air Quality & Noise Level:** Recording of data at already installed analysers and sample collection for monitoring of air quality and noise level are in progress.
- **TERI study on Bioremediation of Sludge:** Application of bio material is planned from today in the affected areas from Plastic Park side to Baghjan blowout well. Clearing of site prior to bio remediation in wetland areas and site preparations for ex/in-situ bio remediation job in affected areas are also in progress.
- **CSIR-NEIST Seismological Study:** Seismological recording carried out by CSIR-NEIST has been completed. Data is being analysed for submission of final report. Other Geo-Physical monitoring is being continued by CSIR- NEIST.
- **IIT- Guwahati Study on Thermal Mapping & Sonic Measurement:** Interpretation of the collected data will be carried out using specialized software at IIT Guwahati and the report will be submitted soon.

Preparation for Capping the Well

- **Final Preparation for Capping Operation:** All operational crew reached site early in the morning today for carrying out the planned capping operation. BOP stack was hooked up with the Athey Wagon for placing on the well head. While the final capping operation was being attempted, the Athey Wagon toppled over at the last moment and the attempt did not succeed. Reasons for the same are being ascertained for next course of action.
- **Final Preparation for Killing Operation:** Well Killing fluid is ready at site.
- **Water Deluge System:** All six numbers of High Discharge CMT Water Pumps are operational at site for spraying water to the well head during the operation. Total 8 nos. of water pumps are available for filling both the water reservoirs periodically.

Relief and Rehabilitation

- **Survey for Damage Assessment:** Survey for assessment of damage for compensation in both Doomdooma and Tinsukia Circle is in progress. Number of families surveyed in Doomdooma and Tinsukia Circle till 30.07.2020 are **596** and **1949** respectively. Total number of families surveyed till 29.07.2020 both combined in Doomdooma and Tinsukia Circle is **2545**.



Law and Order/Bandhs/Blockades etc.

- **Closure of Wells:** Production still continues to be affected due to forceful closure of few Oil & Gas wells connected to Baghjan EPS.
- **Blockade at Drilling/Workover Locations:** Drilling and workover operation still continue to be affected due to forceful closure of operation at few of the locations.

Impact on Oil/Gas Production due to Protests

- Due to stoppage/blockades of several producing wells, there was production loss of 652 MT of Crude Oil and 1.53 MMSCM of Natural Gas as reported on 30-07-2020. Cumulative production loss since 27th May, 2020 due to bandhs and blockades: 18852 MT Crude oil, 44.88 MMSCM of natural gas.

